BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer

SCHEDULE-B

NAME OF WORK: Construction and Repairs to Culverts in Dasarahalli ward no.15

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3	Cum	165.00	129.00	
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	24.75	5122.00	
3	Providing and laying in position plain cement concrete of mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.69 cum and fine aggregtes @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation, plinth and cills, including cost of materials, labour, HOM of machinery, curing complete as per specifications	Sqm	102.09	6680.00	
4	KSRRB M2200-6.TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	10.21	68348.00	
5	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	28.98	1741.00	

Scanned with CamScanner

6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	165.00	65.00	

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned with CamScanner